


LEGEND

- SINGLE GANG LIGHT SWITCH. HAGAR WMPS11
- ARCHITRAVE SWITCH K4841 WHI
- 2 WAY SWITCH. HAGAR WMPS12
- 2 GANG SWITCH. HAGAR WMPS22
- 2 GANG 2 WAY SWITCH. HAGAR WMPS22
- MEGAMAN RENZO BULKHEAD CEILING MOUNTED, LED LAMP 76LM/WM, 10.5W, 3000K. IP44 RATED (BOTH A & B ARE THE SAME PRODUCT)
- UNITY CV2GIP CONTINUOUS EXTRACT. INDEPENDENT FROM LIGHT FITTING C/W BOOST SWITCH. KITCHEN EXTRACT FLOW AS PER SPECIFICATION (UNIT SPECIFIC)
- UNITY CV2GIP CONTINUOUS EXTRACT. BOOST CONTROLLED BY LIGHT FITTING WITH 15 MINUTE OVER-RUN. BATHROOM EXTRACT FLOW AS PER SPECIFICATION (UNIT SPECIFIC)
- ACCESS PANEL SEE ARCHITECTURAL DETAILS
- LAUNDRY EXTRACT TBC



- CDM 2015  
RESIDUAL RISK
- ELECTRICAL
- ELECTRICAL CONTRACTORS SHALL FAMILIARISE THEMSELVES WITH THE INSTALLATION AND EMPLOY SYSTEMS AND METHODS OF WORKING TO REDUCE ANY HAZARDS.
- IF IN DOUBT ASK AND NOTIFY
- ELECTRICITY IS DANGEROUS
- GENERAL
- IT IS UNDERSTOOD THAT A COMPETENT CONTRACTOR FAMILIAR WITH THE WORKS REQUIRED WILL BE APPOINTED AND THAT THEY WILL BE AWARE OF THE STANDARD HAZARDS.

NOTES:

- DO NOT SCALE FROM THIS DRAWING. WORK FROM FIGURED DIMENSIONS ONLY.
  - ALL DIMENSIONS ARE IN MM, UNLESS STATED OTHERWISE.
  - ALL DIMENSIONS TO BE CHECKED ON SITE PRIOR TO CONSTRUCTION OR ORDERING.
  - ANY ERRORS OR OMISSIONS TO BE NOTIFIED TO CITYZEN LIMITED IMMEDIATELY.
  - CONTRACTOR TO READ & CHECK ALL MANUFACTURES LITERATURE AND IMPLEMENT ITS REQUIREMENTS PRIOR TO INSTALLATION OF ANY MATERIALS AND COMPONENTS.
  - CITYZEN LIMITED IS NOT RESPONSIBLE FOR ANY BUILDING WORK THAT IS CARRIED OUT ON SITE.
  - THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL NECESSARY ARCHITECTURAL, STRUCTURAL AND SPECIALIST DRAWINGS, SPECIFICATIONS, SCOPES OF WORK & ROOM DATA SHEETS.
  - ALL MATERIALS AND WORKMANSHIP SHALL CONFORM WITH THE RELEVANT BRITISH AND EUROPEAN STANDARD, SPECIFICATIONS AND CODES OF PRACTICE.
  - IF IN ANY DOUBT, ASK.
- CABLE HOLES THROUGH ISOWALL PANELS TO BE SEALED & GASKETED TO AVOID CHAFFING.
  - TYPICAL CABLES TO BE 6181Y PVC INSULATED SINGLES FOR LOW TEMPERATURES WITH ALL CORES INSULATED INCLUDING CPC. CABLES MUST BE INSTALLED ABOVE 0°C (BUT OPERATING RANGE DOWN TO -15°C)
  - ALL OUTLETS TO BE FLUSH MOUNTED.
  - ALL ELECTRICAL SERVICES TO BE BS7671 AND PART P COMPLIANT C/W CERTIFICATION AND SIGN OFFS.
  - ALL OUTLETS TO BE CLEARLY MARKED.
  - ALL EXTERNAL PENETRATIONS, CABLES, PIPES AND DUCTS TO BE PROVIDED WITH FIRE COLLARS & SLEEVES.
  - SEE DRAWING 1705-301 FOR THE TYPICAL SERVICES INTERNAL CUPBOARD.

FIRE ALARM BY OTHERS

H	27.07.17	LIGHT SWITCHES UPDATED	AG	JS	JS
G	23.06.17	MEGAMAN NOTE REMOVED	JS	JS	JS
F	08.06.17	SWITCH MANUFACTURERS CHANGED. FITTING MOVED. NOTES AMENDED	MJ	JS	JS
E	01.06.17	FIRE ALARM REMOVED	MJ	JS	JS
D	10.05.17	LIGHT AND FIRE ALARM MOVED TO AVOID CLASH	MJ	JS	JS
C	24.04.17	NOTES AMENDED. PRODUCTS ADDED	MJ	JS	JS
B	27.03.17	NOTE AMENDED	MJ	JS	JS
A	03.03.17	POSITIONS CHANGED. POWER ADDED. NOTES ADDED	MJ	JS	JS
REV	DATE	REVISION	DRAWN	CHECKED	APPROVED

COPYRIGHT CITYZEN LIMITED



CLIENT:  
CARGOTEK

DESIGNER:  
JOHN SMITH

PROJECT:  
CARGOTEK 20FT PRODUCT

TITLE:  
LIGHTING & FIRE ALARM  
TYPE 2 CONFIGURATION

SCALE: 1:20 @ A1  
1:40 @ A3  
DATE: 21/02/2017

PURPOSE OF DRAWING:  
CONSTRUCTION

DRAWING: PROJECT REF - DRG NO. (REVISION)  
1705-222 (H)